

# Proceedings of the State Environment Impact Assessment Authority Kerala

Present: Prof. (Dr.) K.P. Joy, Chairman; Dr. J. Subhashini, Member and Sri. James Varghese, I.A.S., Member Secretary.

Sub: SEIAA- Environmental Clearance for the Proposed quarry project in Sy. Nos. 31/1 Part 1, Part-2, 31/1 Part-3, 30/1, 30/2 pt, 31/1-1, 31/1-2 pt, 31/1-3, 31/1-5, 31/1-6, 31/1-7, 31/1-10, 31/5, 31/6, 31/7 at Kalanjoor Village, Konni Taluk, Pathamnamthitta District, Kerala by Sri.T.K.Sundaresan - EC granted - Orders issued.

# STATE ENVIRONMENTAL IMPACT ASSESSMENT AUTHORITY, KERALA

### No. 926/SEIAA/EC4/3892/2015

## Dated, Thiruvananthapuram 16.09.2017

- Ref: 1. Application received on 23.09.2015 from Sri. Ajai Sundaresh., Managing Director, Darshan Granites Pyt. Ltd., Sree Vardhini, Sivankovil Road, Punalur, Kollam District, Kerala State -691305
  - 2. Minutes of the 57th meeting of SEAC held on 16th & 17th June 2016
  - 3. Minutes of the 66th meeting of SEAC held on 19th December 2016
  - 4. Minutes of the 69th meeting SEAC held on 9th & 10th March 2017
  - 5. Minutes of the 67th meeting of SEIAA held on 28th April 2017
  - 6. Affidavit received on 25.05.2017 regarding the transfer of ownership
  - 7. Minutes of the 73rd meeting of SEAC held on 30th & 31st May 2017
  - 8. Minutes of the 71<sup>st</sup> meeting of SEIAA held on 20<sup>th</sup> July 2017
  - 6. Affidavit dt.10.08.17 & 30.08.17 from Sri.T.K.Sundaresan

# **ENVIRONMENTAL CLEARANCE NO.68/2017**

Sri.Ajai Sundaresh., Managing Director, Darshan Granites Pvt. Ltd, Sree Vardhini, Sivankovil Road, Punalur, Kollam District, Kerala State -691305, vide his application received on 23-09-2015 has sought Environmental Clearance under EIA Notification, 2006 for the quarry project in Sy. Nos. 2011 20/1, 2002, 31/5 21/6 & 31/1-1 at Malaginer Vinage, Konni Taluk, Pathamnamthitta District, Kerala for an area of 9.92 hectares. The project comes under Category B, Activity 1(a), (i) as per the Schedule of EIA Notification 2006 (since it is below 50hectares) and as per O.M. No. L-11011/47/2011-IA.II (M) dated 18<sup>th</sup> May 2012 of Ministry of Environment and Forests.

The proposal was placed before 57<sup>th</sup> meeting of SEAC held on 16<sup>th</sup> & 17<sup>th</sup> June 2016. The Committee appraised the proposal based on Form I, pre-feasibility report, mining plan. Proponent informed the committee that the left out area containing Sy. No. 31/1-7 is presently with them and propose to mine in future. Hence the committee deferred the item for the production of revised mining plan including the above bit of land to make the mining more scientific and environmental friendly. Shri.T.K.Sundaresan has submitted the revised Form 1 and CSR and the revised Mining Plan including the bit of land (Sy. No. 31/1-7) according to the decision of SEAC. In addition to the above Survey No. the new Mining Plan also covers the Survey Nos. such as 31/1-2 pt, 31/1-3, 31/1-5, 31/1-6, 31/1-10 & 31/7 with a total area of 15.07 ha. As per the old Mining Plan and application the total area was only 9.92 ha. The Proponent has also remitted an additional amount of Rs.50,000/- towards the processing fee.

Details of the project as furnished by the applicant are as follows;

## BASIC INFORMATION OF QUARRY

( To be filled in by the Project Proponent)

#### PART A

and expery date of lease/permit period (Copy to be attached)  Present Status of the    Copy to be attached   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the lease/permit period (Copy to be attached)   Present Status of the l		A ANTA					
2. Name / Title of the project Mineral) project of M/s Darshan Granites Pvt. Ltd.  Mineral) project of M/s Darshan Granites Pvt. Ltd.  Mr. T.K. SUNDARESAN, (Managing Director), M/s DARSHAN GRANITES PVT. LTD.  "Aswathy", Sivankovil Road, Punalur, Kollam District, Kerala-691305  The project site is partially private owned land (2.86 ha.) an partially Govt. land (12.21 ha.) on lease for mining activities.  Survey No. District / Taluk / and Village etc.  Details of period of lease or permit with number including the beginning and expiry date of lease/permit period (Copy to be attached)  Present Status of the		Project details					
Mineral) project of M/s Darshan Granites Pvt. Ltd.  Mr. T.K. SUNDARESAN, (Managing Director), M/s DARSHAN GRANITES PVT. LTD.  Aswathy", Sivankovil Road, Punalur, Kollam District, Kerala-691305  The project site is partially private owned land (2.86 ha.) an partially Govt. land (12.21 ha.) on lease for mining activities.  Survey No. District/ Taluk / and Village etc.  Details of period of lease or permit with number including the beginning and expiry date of lease/permit period (Copy to be attached)  Present Status of the	1.	File No.					
Mr. T.K. SUNDARESAN, (Managing Director), M/s DARSHAN GRANITES PVT. LTD.  *Aswathy*, Sivankovil Road, Puralur, Kollam District, Kerala-691305  The project site is partially private owned land (2.86 ha.) an partially Govt. land (12.21 ha.) on lease for mining activities.  Survey No. District/ Taluk / and Village etc.  Details of period of lease or permit with number including the beginning and expiry date of lease/permit period (Copy to be attached)  Present Status of the  Mr. T.K. SUNDARESAN, (Managing Director), M/s DARSHAN GRANITES PVT. LTD.  *Aswathy*, Sivankovil Road, Puralur, Kollam District, Kerala-691305  The project site is partially private owned land (2.86 ha.) an partially Govt. land (12.21 ha.) on lease for mining activities.  Survey No. 31/1 Part 1, 2 & 3, 30/1, 30/2pt, 31/1-1, 31/1-2p. 31/1-3, 31/1-5, 31/1-6, 31/1-7, 31/1-10, 31/5, 31/6, 31/ Kalanjoor Village, Konni Taluk, Pathanamthitta District, Kerala vide E. C. Order in SEIAA, Kerala vide E. C. Order in 435/SEIAA/EC4/2995/2014 dt. 23-12-2015 in the mane of M Darshan Granites (P) Ltd. and this area also got merged with the current application		Name /Title of the					
3. Name and address of project proponent.  M/s DARSHAN GRANITES PVT. LTD.  "Aswathy", Sivankovil Road, Punalur, Kollam District, Kerala-691305  The project site is partially private owned land (2.86 ha.) ar partially Govt. land (12.21 ha.) on lease for mining activities.  Survey No. District / Taluk / and Village etc.  Details of period of lease or permit with number including the beginning and expiry date of lease/permit period (Copy to be attached)  Present Status of the  M/s DARSHAN GRANITES PVT. LTD.  "Aswathy", Sivankovil Road, Punalur, Kollam District, Kerala-691305  The project site is partially private owned land (2.86 ha.) ar partially Govt. land (12.21 ha.) on lease for mining activities.  Survey No. 31/1 Part 1, 2 & 3, 30/1, 30/2pt, 31/1-1, 31/1-2p 31/1-3, 31/1-5, 31/1-6, 31/1-7, 31/1-10, 31/5, 31/6, 31/ Kalanjoor Village, Konni Taluk, Pathanamthitta District, Kerala vide E. C. Order in 435/SEIAA/EC4/2995/2014 dt. 23-12-2015 in the name of M Darshan Granites (P) Ltd. and this area also got merged with current application	2.	project					
3. project proponent.  4. Owner of the land  5. Survey No. District/ Taluk / and Village etc.  Details of period of lease or permit with number including the beginning and expiry date of lease/permit period (Copy to be attached)  Present Status of the land  4. Owner of the land  Survey No. District / Taluk / and Village etc.  Survey No. 31/1 Part 1, 2 & 3 , 30/1, 30/2pt, 31/1-1, 31/1-2p 31/1-3, 31/1-5, 31/1-6, 31/1-7, 31/1-10, 31/5, 31/6, 31/Kalanjoor Village, Konni Taluk, Pathanamthitta District, Keral existing mine of 4.07 hectare (Govt. Land) within cluster are for production capacity of 1,60,000 MTA is already approve from SEIAA, Kerala vide E. C. Order nearne of M Darshan Granites (P) Ltd. and this area also got merged with the current application							
Punalur, Kollam District, Kerala-691305  4. Owner of the land  Survey No. District / Taluk / and Village etc.  Details of period of lease or permit with number including the beginning and expiry date of lease/permit period (Copy to be attached)  Punalur, Kollam District, Kerala-691305  The project site is partially private owned land (2.86 ha.) and partially Govt. land (12.21 ha.) on lease for mining activities.  Survey No. 31/1 Part 1, 2 & 3 , 30/1, 30/2pt, 31/1-1, 31/1-2p 31/1-3, 31/1-5, 31/1-6, 31/1-7, 31/1-10, 31/5, 31/6, 31/ Kalanjoor Village, Konni Taluk, Pathanamthitta District, Keral Existing mine of 4.07 hectare (Govt. Land) within cluster are for production capacity of 1,60,000 MTA is already approve from SEIAA, Kerala vide E. C. Order n 435/SEIAA/EC4/2995/2014 dt. 23-12-2015 in the name of M Darshan Granites (P) Ltd. and this area also got merged with the current application	2	Name and address of	· · · · · · · · · · · · · · · · · · ·				
The project site is partially private owned land (2.86 ha.) are partially Govt. land (12.21 ha.) on lease for mining activities.  Survey No. District / Taluk / and Village etc.  Details of period of lease or permit with number including the beginning and expiry date of lease/permit period (Copy to be attached)  Present Status of the  The project site is partially private owned land (2.86 ha.) are partially Govt. land (12.21 ha.) on lease for mining activities.  Survey No. 31/1 Part 1, 2 & 3 , 30/1, 30/2pt, 31/1-1, 31/1-2pt 31/1-3, 31/1-5, 31/1-6, 31/1-7, 31/1-10, 31/5, 31/6, 31/6 Kalanjoor Village, Konni Taluk, Pathanamthitta District, Keral Existing mine of 4.07 hectare (Govt. Land) within cluster are for production capacity of 1,60,000 MTA is already approved from SEIAA, Kerala vide E. C. Order in 435/SEIAA/EC4/2995/2014 dt. 23-12-2015 in the name of M Darshan Granites (P) Ltd. and this area also got merged with the current application	ا ع.	project proponent.	"Aswathy", Sivankovil Road,				
partially Govt. land (12.21 ha.) on lease for mining activities.  Survey No. District  Taluk / and Village etc.  Details of period of lease or permit with number including the beginning and expiry date of lease/permit period (Copy to be attached)  Present Status of the  partially Govt. land (12.21 ha.) on lease for mining activities.  Survey No. 31/1 Part 1, 2 & 3 , 30/1, 30/2pt, 31/1-1, 31/1-2pt 31/1-3, 31/1-5, 31/1-6, 31/1-7, 31/1-10, 31/5, 31/6, 31/6, 31/6, 31/1-3, 31/1-5, 31/1-6, 31/1-7, 31/1-10, 31/5, 31/6, 31/6, 31/1-3, 31/1-3, 31/1-4, 31/1-4pt 31/1-2pt 31/1-3, 31/1-5, 31/1-6, 31/1-7, 31/1-10, 31/5, 31/6, 31/6, 31/6, 31/6, 31/1-3, 31/1-3, 31/1-4, 31/1-4pt 31/1-3, 31/1-4pt 31/1-4pt 31/1-3, 31/1-4pt 31/1-3, 31/1-4pt 31/1-3, 31/1-4pt 31/1-3, 31/1-4pt 31/1-4pt 31/1-4pt 31/1-3pt 31/1-4pt 31/1	,						
Survey No. District / Taluk / and Village etc.  Details of period of lease or permit with number including the beginning and expiry date of lease/permit period (Copy to be attached)  Present Status of the  Survey No. 31/1 Part 1, 2 & 3 , 30/1, 30/2pt, 31/1-1, 31/1-2p 31/1-3, 31/1-5, 31/1-6, 31/1-7, 31/1-10, 31/5, 31/6, 31/ Kalanjoor Village, Konni Taluk, Pathanamthitta District, Keral Existing mine of 4.07 hectare (Govt. Land) within cluster are for production capacity of 1,60,000 MTA is already approve from SEIAA, Kerala vide E. C. Order n 435/SEIAA/EC4/2995/2014 dt. 23-12-2015 in the name of M Darshan Granites (P) Ltd. and this area also got merged with the current application			The project site is partially private owned land (2.86 ha.) and				
5. Survey No. District / Taluk / and Village etc.  Details of period of lease or permit with number including the beginning and expiry date of lease/permit period (Copy to be attached)  Present Status of the  31/1-3, 31/1-6, 31/1-7, 31/1-10, 31/5, 31/6, 31/Kalanjoor Village, Konni Taluk, Pathanamthitta District, Keral Existing mine of 4.07 hectare (Govt. Land) within cluster are for production capacity of 1,60,000 MTA is already approve from SEIAA, Kerala vide E. C. Order name of M Darshan Granites (P) Ltd. and this area also got merged with current application	4.	Owner of the land					
Details of period of lease or permit with number including the beginning and expery date of lease/permit period (Copy to be attached)  Taluk / and Village etc.  Kalanjoor Village, Konni Taluk, Pathanamthitta District, Keral Existing mine of 4.07 hectare (Govt. Land) within cluster are for production capacity of 1,60,000 MTA is already approve from SEIAA, Kerala vide E. C. Order in 435/SEIAA/EC4/2995/2014 dt. 23-12-2015 in the mane of M Darshan Granites (P) Ltd. and this area also got merged with the current application							
Details of period of lease or permit with number including the beginning and expiry date of lease/permit period (Copy to be attached)  Details of period of lease Existing mine of 4.07 hectare (Govt. Land) within cluster are for production capacity of 1,60,000 MTA is already approve from SEIAA, Kerala vide E. C. Order not described the name of M Darshan Granites (P) Ltd. and this area also got merged with the current application	5.		$\begin{bmatrix} 31/1-3, & 31/1-5, & 31/1-6, & & 31/1-7, & 31/1-10, & 31/5, & & & & & & & & & & & & & & & & & & &$				
or permit with number including the beginning and expiry date of lease/permit period (Copy to be attached)  or permit with number for production capacity of 1,60,000 MTA is already approved from SEIAA, Kerala vide E. C. Order number of Matter and Ease/permit period (Copy to be attached)  Present Status of the		Taluk / and village etc.	Kalanjoor Village, Konni Taluk, Pathanamthitta District, Kerala				
including the beginning and expiry date of lease/permit period (Copy to be attached)  Present Status of the		Details of period of lease	Existing mine of 4.07 hectare (Govt. Land) within cluster area				
and expiry date of lease/permit period (Copy to be attached)  Present Status of the  435/SEIAA/EC4/2995/2014 dt. 23-12-2015 in the name of M Darshan Granites (P) Ltd. and this area also got merged with the current application		or permit with number					
and expiry date of lease/permit period (Copy to be attached)  Present Status of the  435/SEIAA/EC4/2995/2014 dt. 23-12-2015 in the name of M Darshan Granites (P) Ltd. and this area also got merged with the current application		including the beginning					
lease/permit period (Copy to be attached)  Present Status of the  Darshan Granites (P) Ltd. and this area also got merged with the current application	Ð.,						
Present Status of the		T . T	Darshan Granites (P) Ltd. and this area also got merged with				
THE PROPERTY AND THE PR		(Copy to be attached)	the current application				
04/10/2015 ( 4.07 ha with EC from SEIA A)	7.	· • • • • • • • • • • • • • • • • • • •					
project 24/12/2013 (4.07 ha with EC from SEIAA)		project	24/12/2015 ( 4.07 ha with EC from SEIAA)				
a. Date & Year of							
starting the work of the Mining area for 4.07 ha is working quarry with EC from		starting the work of the	Mining area for 4.07 ha is working quarry with EC from				

·	quarry project.	CETA A
	b. whether the quarry is	SEIAA within the cluster area.
ŀ	working at present or no	
	c. If stopped working	110, 110t applicable
	since when?	
		22/09/2015 ( Application submitted )
		The application was submitted at SEIAA on 22-09-2015 in the
		name of M/s Sahyadri Quarries & Granites (P) Ltd. for an area
		of 9.92 ha, and the project was deferred by SEAC in its 57th
	D-4 C 1	meeting held on 16th & 17th June, 2016 (Item No. 57.11) for
8.	Date of submission of	submission of revised application with cluster area.
	Application	The NOC issued for mining in Goyt, land for an area of 8.14 ha.
		for a period of 12 years was issued by District Collector
		Pathanamthitta in favour of M/s Sahyadri Quarries and Granites
		Pvt. Ltd. was cancelled and same was issued in favour of M/s
		Darshan Granites Pvt. Ltd. for the same area and for the same period.
		The land for the proposed quarry with cluster area is partially
		private owned land (2.86 ha) and partially Govt. land (12.21 ha)
		and the land is possessed in name of M/s Darshan Granites (P)
9.	Brief description of the	Ltd. The targeted production of mine will be 6,15,900 MTA.
	project.	The estimated project cost will be Rs. 9 Crores. The life of mine
		estimated will be of about 14 years. The mining operation will
		be carried out by opencast semi-mechanized method as per
		approved Mining Plan.  M/s Darshan Granites (P) Ltd.,
10	Details of Authorized	- Bid. 展展 ●
10.	Signatory and address fo correspondence	Aswathy", Sivankovil Road, Punalur,
	correspondence	Kollam District, Kerala-691305
		Land Details
11.		15.07 ha
- :	in hectares	[Govt. Land (12.21 ha) + Private own land (2.86 ha)]
	Is the	
	property forest	
12.		Govt. Land (12.21 ha) + Private own land (2.86 ha)
	land /own	Government (12:21 ha) + ( Hvate own land (2:00 ha)
	land/patta	
	land	
	7.5	A total quantity of 19,052 cu. m. of topsoil is proposed to be
!		removed during the mining operations. The topsoil excavated from
	Duantity of	the quarry will be dumped / stacked separately at pre-determined
	ton soil /over	place and subsequently will be utilized in spreading over reclaimed
13.	hurden	areas for plantation as part of eco-restoration. Precautions will be
	1 1	taken to limit the height of the topsoil dump / stacked to 5 to 6
	managed	meters in order to preserve its fertility and shelf life. It will be
		suitably protected from soil erosion and infertility by planting fodder grass and leguminous plants during temporary storage.
		About 13,449 cu. m of overburden (OB) will be generated
		or overbuilden (OD) will be generated

<del></del>	<u> </u>	I was the mine life This wests will be willized within the	nit ]
		throughout the mine life. This waste will be utilized within the properties of haul roads. At the end use, OB can be reutilized as so base for plantation.	oil
	1 T	Latitude (N) 09°08'57.15"N to 09°09'12.93"N	$\neg \neg$
14.	1. Latitude and Longitude	Longitude (E) 76°54'20.35"E to 76°54'42.60"E	
15.	2. Topography of land and elevation	Part of the proposed land is covered with native trees, shrul herbs, grass, climbers, bushes etc. The highest elevation of the lease area is 235 m MSL and lowest is 170 m MSL	bs, the
16.	3. Slope analysis	Slope Towards South side	
17.	4. Will there be any significant land disturbance resulting in soil erosion, subsidence & natural drainage.	Due care will be taken to provide channel all around the foot hill to collect run off and also to avoid soil erosion.  There is no danger of flood or inundation as the proposed worki is above the normal ground level. The area is not susceptible flood.	ing
18.	Access road to the site width and condition	7m wide tarred road	
19.	Will there be any adverse impact on the aesthetics of the proposal	No, the land used will be fully reclaimed and rehabilitated backfilling the pits and plantation and pond. Plantation afforestation will add to the improvement in environment a aesthetic beauty of the area.	and
	site	Mining details	
20.	Minimum and Maximum heig of excavation.	The exploitation of mineral is being done from 235 m to 16:	5m
21.	Life of mine proposed.	About 14 years	
22.	Underground mining if any proposed	No underground mining proposed.	
23.	Method of Mining	The working will be carried out by opencast semi-mechanizmethod as per the approved Mining Plan	
24.	Distance from tadjacent quarry	An Environment Clearance was issued by SEIAA Kerala for area of 4.07 ha. (Govt. land) which is in contiguity with the a under consideration. Existing mine of 4.07 hectare wit cluster area for production capacity of 1,60,000 MTA vapproved from SEIAA, Kerala vide E. C. Order 435/SEIAA/EC4/2995/2014 dt. 23-12-2015 in the name of N Darshan Granites (P) Ltd. and this area also got merged w	hin was

				the current application.	
25.		a)	Cluster condition if any	Existing mine of 4.07 hectare within cluster area for production capacity of 1,60,000 MTA is already approved from SEIAA, Kerala vide E. C. Order no. 435/SEIAA/EC4/2995/2014 dt. 23-12-2015 in the name of M/s Darshan Granites (P) Ltd. and this area also got merged with the current application.	
26.		b)	Has "No cluster certificate" submitted?	The revised application for cluster area was submitted as per the directions of Hon'ble SEAC, Kerala.	
27.		c)	Distance from nearby habitation	Nearest house is about 116m towards SE side	
28.		d)	Distance from nearby forest, if applicable	Teak forest about 500m towards \$W     Konni Reserve Forest, 6 km, E	
29.		e)	Distance from protected area, Wildlife Sanctuary, National Park etc.	None within the study area	
30.		f)	Distance from nearby streams / rivers /National Highway and Roads	Water bodies near site:-  1. Achankovil River = 6 km, E  2. Achankovil drain - 3 km., NE  3. Kallada River - 15 km., S  4. Thodu / drain - about 5 km, W	
31.		g)	Is ESA applicable? If so distance from ESA limit	Not falling in ESA	
32.		h)	Has approved mining plan, prepared by RQP submitted?	Yes, the approved mining plan prepared by RQP is already submitted along with E.C. Application	
33.		i)	Capacity of production in TPA	6,15,900 MTA	
34.		j)	Details of mining process	The mining will be done by open cast semi-mechanized method of mining. The bench height and width will be maintained 5 m. Excavated material is transported to the crusher unit within the complex for further processing. The exploitation of mineral is being done from 235 m to 165m MSL in conceptual phase.	
	Details of Project cost				
35.	a)	Lan	d cost	Rs. 9 Crores (All inclusive)	
36.	<u>b)</u>	•	nt and Machinery	Rs. 9 Crores ( All inclusive )	
37.	c)		al Cost	Rs. 9 Crores (All inclusive)	
38.	10			Rs. 9 Crores (All inclusive) Insurance = Insurance to the quarry workers would	
	Statement including			moutance - moutance to the quarty workers would	

funding sourceand details of insurance		ugh insurance company. wn source & bank loan
etc.		
details of insurance		Mining activities will generate certain quantities of dust during drilling, blasting, loading and transportation operations. The following measures will be taken to mitigate the fugitive dust from different operations.  Laying of haul road as per the standards, black topping of permanent haul road and service road to avoid or eliminate air—borne dust.  To avoid the dust generation from the drilling operations, wet drilling method will be adopted.  Drill machines will be equipped with dust collectors.  Use of appropriate explosives for blasting and avoiding overcharging of blast holes.  Controlled blasting techniques will be adopted.  Watering of haul road and other road at regular intervals.  Provision of dust filters/ mask to workers working at highly dust prone and affected areas.  Provision of green belt all along the periphery of the lease area.  Periodical monitoring of ambient air quality in and around the lease area.  The extracted mineral will be transported from the quarry to the end user by adopting following measures so as to minimize dust emissions.
		<ul> <li>In case of long transportation the trucks after loading will be covered with tarpaulin sheets.</li> <li>Speed of the vehicles will be maintained within the prescribed limits.</li> <li>Trucks will not be over loaded and will be maintained to the body level</li> </ul>
	Water Pollution	Provision of storm water collection pond with an appropriate capacity. The water requirement
		for sprinkling on sources of dust emission, on roads, landscaping etc. Can be met from the
	Noise	stored rainwater in the pond.  The major noise generating source from the
		proposed activity is working machinery, drilling, blasting and plying of vehicles. The

_	· · · · · · · · · · · · · · · · · · ·		
			following control measures are to be undertaken
	1		to bring down the noise levels:-
			> Proper maintenance of machinery,
			equipments and improvement on design of
			machines.
			Use of personal protective devices i.e.,
			earmuffs and earplugs by workers, who are
			working in high noise generating areas.
•			> Creation of wide green belt of dense foliage
			between mine areas and residential colonies.
			Proper training to personnel to create
			awareness about adverse noise level effects.
			> Planned noise monitoring at suitable locations
			in the plant and outside location for proper
			effective remedial actions
		Solid Waste	
		Management	<b>F</b>
		management	The topsoil excavated from the quarry will be
1		[] ·	dumped / stacked separately at pre-
			determined place and subsequently will be
			utilized in spreading over reclaimed areas for
			plantation as part of eco-restoration.
			Precautions will be taken to limit the height
	e e e e e e e e e e e e e e e e e e e		of the topsoil dump / stacked to 5 to 6 meters
]		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	in order to preserve its fertility and shelf life.
			It will be suitably protected from soil erosion
			and infertility by planting fodder grass and
			leguminous plants during temporary storage.
			Overburden Management
			This waste (OB) will be utilized within the pit
i			
ĺ.,			for lying of haul roads. At the end use, OB can
			be reutilized as soil base for plantation.
		Eco-	The year wise programme of eco-restoration
	illi Tilliga om statistiska om statistiska om statistiska om statistiska om statistiska om statistiska om statistis	restoration	for life of mine will be made and about 9,700
			trees will be planted in an area of 9.70 ha.
	The second secon	<u> </u>	(8.5914 ha + 1.1086 ha outside).
	VI. Whether	Yes.	
	Environment		
40.	Management Plan or Eco		
	restoration Plan		·
	satisfactory?		
	VII. Does it suggest	Detailed Envir	onment Management Plan is already submitted
41.	mitigation measures for	with E.C. Appl	
	each activity	with the table	iomoni.
	VIII. If Pre-Feasibility	Datailed Bee E	posibility Deposit (DED) is also do 1 to 1 to 1
42			easibility Report (PFR) is already submitted with
42.	Report (PFR)	E.C. Application	on.
	satisfactory		
43.	IX. Does it need	Not Applicable	
	public hearing		
44.	X. Details of	No litigation pe	ending.

	100	
	litigation and Court	
_	verdict if any	NT.
45.	XI. Details of public	None
	complaint, if any	The Calleging Cost Orders / Policies are to be followed:
	WII Data II- a C	The following Govt. Orders / Policies are to be followed:  Consents from Kerala State Pollution Control Board.
1	XII. Details of	> Permission from Mining & Geology Department.
46.		<ul> <li>Permission from Explosive Department</li> </ul>
	required	> Permission from Panchayat Office.
<u> </u>	XIII.If CRZ	Not Applicable
47.		Not Applicable
7/.	applicable?	
	пррисиоте:	PART B
	Environment	Impact Assessment and Mitigation Measures
		Impact on water
		The total water requirement is about 17 KLD in which 2 KLD
	a) Details of water	is for domestic which would be sourced from open well, 13
48.	requirement per day	KLD for dust suppression system in mine as well as ancillary
	in KLD	units and 2 KLD for plantation will be sourced from storm
		water pond.
	·	2 KLD for domestic which would be sourced from open well,
49.	b) Water source/sources.	13 KLD for dust suppression system in mine as well as
<del>1</del> 2.	Water source/sources	ancillary units and 2 KLD for plantation will be sourced from
		storm water pond.
	c) Expected water use	2 KLD for domestic requirement, 13 KLD for dust suppression
50.	per day in KLD.	system in mine as well as ancillary units and 2 KLD for
		plantation
	d) Details of water	Nil
51.	requirements met from water	
	harvesting.	
	e) What are the impact	No significant impact envisaged on ground water due to the
52.	of the proposal on the	mining project.
22.	ground water?	The state of the s
	f) How much of the	Nil
	water requirement	
	can be met from the	·
53.	recycling of treated	·
	waste water?	·
	(Facilities for liquid	
	waste treatment)	
	g) What is the	The sewage to a tune of 1.60 KLD generated from the mine
1 1 1 1	incremental pollution	office will be diverted to the septic tank followed by soak pit.
54.	load from waste	
57.	water generated from	
	the proposed	
	activities?	N Ct
55.	h) How is the storm	Storm water drains with silt traps will be suitably
	water from within the	constructed all along the periphery of the pit area to collect

		- 10					
		site managed?	<ul> <li>the run-off from the lease area and divert into the storm water pond/tanks proposed within the complex.</li> <li>All measures will be taken not to disturb the existing drainage pattern adjacent to the other property.</li> <li>De-siltation traps and storm water collection pond proposed for silt removal.</li> <li>The storm water collected from the lease area will be utilized for dust suppression on haul roads, plantation within the premises etc.</li> </ul>				
L		Impact on I	Biodiversity and Eco restoration Programmes				
56	a)	Will the project involve extensive clearing or modification of vegetation (Provide details)	Due to the mining activities, there will be loss of some native species and vegetation. However, some of these species will be planted at the end use for eco-restoration.				
	<del>                                     </del>		The year wise programme of one posteration for 116 of the				
57		What ate the measures proposed to minimize the likely impact on vegetation (details of proposal for tree plantation/landscaping)	Next Six months onwards Trees Selection of species is based on High Dust Capturing, Soil				
			Holding Capacity, ground water recharge capacity etc. More focus is given for medicinal plants.				
58.		Is there any displacement of fauna — both terrestrial and aquatic. — If so what are the mitigation measures?  Presence of any endangered species or red listed category (in detail)	Not applicable  No endangered species found at site				
	Impact on Air Environment						
59.	a)	What are the mitigation measures on generation of dust, smoke and air quality	Details already provided at EMP section at Sr. No. 39 above.				
60.		Details of internal traffic management of the site.	Designated space will be provided for parking of truck / tipper within the site. For the purposes of mining activities, existing roads are sufficient. However, haul road will be suitably developed within the proposed area. Speed of the vehicles will be maintained within the prescribed limits (Speed Governor fitted).				
61.	<u>c)</u>	Details of noise from					

		troffic machines and	Details already provided at EMP section at Sr. No. 39 above.
		traffic, machines and vibrator and	Details affeatly provided at EIVIF Section at St. 140, 33 above.
		mitigation measures	
	d)	Impact of DG sets	Details already provided at EMD coation at Sr. No. 30 shave
		and other equipments	Details already provided at EMP section at Sr. No. 39 above.
		on noise and	
62.		vibration and	
		ambient air quality	·
		around the project	
		site and mitigation	
		measures	Details already provided at EMP section at Sr. No. 39 above.
63.	e)	Air quality	Details already provided at Elvir section at 51, 140, 59 above.
		monitoring in detail	TConservation
<u> </u>		D.4.11 C	Energy Conservation  The total power requirement will be 75 kW, which will be
	a)	Details of power	drawn from diesel engine. Fuel Quantity 16 to 20 lt/hr.
64.		requirement and	mawn nom meser engine. Puer Quantity— to to 20 to in.
	1. \	source of supply.	Wa will promote renovehle energy recourses
	b)	Details of renewable	We will promote renewable energy resources.
65.		energy (non –	
		conventional) used.	Risk Management
<del></del>		A 41 CC .:4	Risk Management
	a)	Are there sufficient	
		measures proposed for risk hazards in	Detailed Environment Management Plan is already submitted
66.		case of emergency	with E.C. Application.
		such as accident at	with E.C. Application.
		the site?	A 2000 (1900 )
		24 (44 C) -	Barbed wire fencing will be done all around the quarry site.
	b)	Are proposals for	Barbed with tenents will be done air around the dearly store
		fencing around the	The stone quarry mine will result in increase in frequency of
		quarry satisfactory?	blasting for mining the mineral. However, controlled blasting with
			optimum charge of holes will be carried out to loosen the rock.
	c)		Explosion hazards are envisaged due to mishandling of explosives.
67.		/hazardous substance	Explosives will be handled with utmost care in compliance of
		in detail	conditions imposed by Chief Controller of Explosive &
			Metalliferous Mines Regulation, 1961.
	al v		Top soil and over burden generated from the site will be stored
	d)	Facility for solid	separately on earmarked place and will be used for eco-restoration
		waste management	and internal road development.
	<u> </u>		Socio Economic Impacts
·	1)	Will the project	No
		cause adverse effects	
		on local communities	
		disturbance to sacred	
68.		sites or other cultural	
		values. What are the	
.		safe guards	
		proposed?	
		proposed?	

69	result in any changes	The mining project will directly / indirectly develop the area by providing employment opportunities. With the proposed development in and around the area there will be many supporting facilities/ infrastructure eventually leading to the development of the area.
70	3) Are the CSR	Yes. A detailed study on social status of the project site surroundings & need base study on proposed CSR activities were carried out and report was submitted with EC Application. The project proponent will set apart Rs. 13 lakhs (recurring) and Rs. 12 Lakhs (non-recurring) for taking up for welfare activities for the local community in consultation with the local body.
71	4) What are the projects benefits in terms of employment potential?	Due to the mining activity and due to the attached ancillary unit, there will be workers attracted to the project area. It is proposed to employ 40 persons in the project.
	potenzazy	PARTIC
72	Details of NABET approved EIA Consultant engaged- Their name, address and accreditation details	M/s Environmental Engineers & Consultants Pvt. Ltd. (NABET Accredited Consultant Organization)  Head Office:- A1-198, Janak Puri, New Delhi.  Branch Office:- C-306, Kanchanjunga Apartments, Palarivattom P.O., Kochi, Kerala.
7	a) Overall justification for implementation of the project.	It is predicted that socio-economic impact due to this project will positively increase the chance of more employment opportunities for local inhabitants. There are no Resettlement and Rehabilitation issues involved in this project. The project infrastructures will be of use to people of the area. The revenue of the State Govt. will be definitely increasing due to the proposed activity. The entire project area is devoid of any endangered flora and fauna. It is proposed to reclaim the land and develop green cover for eco-restoration with native species to a maximum possible extent. Additionally, an area is earmarked outside the proposed mining area for compensatory mass plantation. Also, a storm water pond is proposed outside the mining area for storage of rain water and for its subsequent use so as to conserve fresh water consumption. Thus the proposed project is not likely to affect the environment or adjacent ecosystem adversely.
7	b) Explanation of how adverse impact have been mitigated.	Detailed Pre-Feasibility Report (PFR) with Environment Management Plan (EMP) is already submitted with E.C. Application.

3. The proposal was considered in the 66<sup>th</sup> meeting of SEAC held on 19<sup>th</sup> December, 2016 and decided to defer the item for site inspection.

Subsequently, field visit to the Quarry project was carried out on 25.02.2017 by the sub-committee of SEAC comprising Dr. Keshav Mohan and Sri. John Mathai and the report is as follows;

This proposal was originally submitted in the name of M/s Sahyadri Quarries & Granites Pvt Ltd with Sri. Ajai Sundaresh as the proponent. Meanwhile, based on the request, the District Collector cancelled the NOC obtained in the name of M/s Sahyadri Quarries & Granites Pvt Ltd and awarded NOC for the same land to M/s Darsan Granites Pvt Ltd with Sri. T.K. Sundaresan as the proponent. M/s Darsan Granites Pvt Ltd operates a quarry in 4.07 ha area located adjacent to the applied lease area and issued with EC which expired on 25.11.2016. Now as suggested in the SEAC meeting, Sri. T.K. Sundaresan has submitted revised approved mine plan for the combined area of 15.07 ha(govt.land and own land) in the name of M/s Darsan Granites Pvt Ltd. The site inspection was carried out in this 15.07 ha of land.

This project is located at about 4 km east of Athirunkal with its approach from Murinjakal on the Pathanapuram-Konni road. Boundary pillars of the combined plot are erected and numbered as given in the surface plan. Entire area has been provided with fence. The rock type is a mixture of Khondalite and Charnockite. The western part is partly exploited with formation of benches while the eastern part exposes hard rock with its major part sloping to south. The storm water from the worked out portion is channelized into a pit on the southern part that functions as RWH structure and overflow let out through a defined channel after clarification. The service block and a crusher unit are located on the extreme southern part. The main haulage road and the approach road are properly laid. Floral and faunal biodiversity is not observed as the area is mostly rocky and disturbed. Dwelling units are not observed in the vicinity. The nearest quarry of M/s Mavanal is more than 500 m from the periphery. A forest patch is noticed on the southern side but beyond 200 m. Based on an overall evaluation of the site and considering the fact that the site includes a part where EC was already issued, it can be recommended subject to the following conditions.

- 1. Mandatory sign boards are to be in place.
- 2. Storm water flow to the south-eastern part must be channelized into another RWH which need to be developed during the progressive quarry operation.
- 3. More number of sprinklers is to be provided around the crusher unit to suppress dust.
- 4. The proposal was placed in the 69<sup>th</sup> meeting SEAC held on 9<sup>th</sup> & 10<sup>th</sup> March 2017. The Committee observed that "The Original application is on behalf of Sahyadri Quarries by Sri.AjaiSunderesh. Now for a revised proposal, inclusive of the area proposed by Sahyadri Quarries, is submitted in the name of Darshan Granites by Sri.T.K.Sundaresan, father of Sri.AjaiSunderesh. The Committee decided to defer the item for appropriately reprocessing the file by SEIAA after realising the required fees".

This proposal was originally submitted in the name of M/s Sahyadri Quarries & Granites Pvt Ltd with Sri. Ajai Sundaresh, Managing Director as the proponent on 22.09.2015 for an area of 9.92 ha. They paid processing fee by DD for an amount of Rs. 2

lakhs. Meanwhile, based on the request, the District Collector cancelled the NOC obtained in the name of M/s Sahyadri Quarries & Granites Pvt Ltd and issued NOC for the same land to M/s Darshan Granites Pvt Ltd with Sri. T.K. Sundaresan as the proponent. M/s Darshan Granites Pvt Ltd operates a quarry in 4.07 ha area located adjacent to the applied lease area and issued with EC which expired on 25.11.2016. On the basis of NOC from District Collector, they approached Mining and Geology department for Letter of Intent (LOI) as per KMMCR 2015 for the cumulative area of 15.07 ha. in the name of M/s Darshan Granites pvt ltd. Now as suggested in the SEAC meeting, Sri. T.K. Sundaresan has submitted revised approved mine plan for the combined area of 15.07 ha (govt. land and own land) in the name of M/s Darsan Granites Pvt Ltd.

The proponent already submitted the additional processing fee for total area. So the proposal was considered as new file in the name of Sri.T.K.Sundaresan, Managing Director, M/s Darshan Granites.

- 5. The proposal was placed in 67<sup>th</sup> meeting of SEIAA held on 28<sup>th</sup> April 2017. The Authority decided to consider the proposal on submission of a revised application for the transfer of ownership in the name of Sri.T.K.Sundaresan, Managing Director, M/s Darshan Granites and return the proposal to SEAC for reappraisal. The proponent has submitted an affidavit giving consent for the transfer of ownership to Sri.T.K.Sundaresan.
- 6. The proposal was considered in the 73<sup>rd</sup> meeting of SEAC held on 30<sup>th</sup> and 31<sup>st</sup> May 2017. Consequent to the changes in the ownership and area, the 69<sup>th</sup> meeting of the Committee had recommended to reprocess the application. Accordingly SEIAA accepted a revised application and decided to consider it. The Committee appraised the proposal based on the Mining Plan, Pre-feasibility Report, field visit report and all other documents submitted along with Form1 and decided to Recommend for Issuance of EC subject to the general conditions along with following specific condition.
  - 1. If any plant species endemic to Western Ghats are noticed in the area they shall be properly protected in situ or by transplanting to an appropriate location inside the lease area.
    - 2. Storm water flow to the south-eastern part must be channelized into another RWH which need to be developed during the progressive quarry operation.

The proponent should set apart Rs.13 lakh (recurring) and Rs.12 lakh(non-recurring) for taking up welfare activities for the local community in consultation with the local body.

- 7. The proposal was finally considered in the 71<sup>st</sup> meeting of SEIAA held on 20<sup>th</sup> July 2017. Authority accepted the recommendation of SEAC and decided to issue EC subject to general condition in addition to the following specific conditions.
  - 1. If any plant species endemic to Western Ghats are noticed in the area they shall be properly protected in situ or by transplanting to an appropriate location inside the lease area.
  - 2. Storm water flow to the south-eastern part must be channelized into another RWH which need to be developed during the progressive quarry operation.
  - 3. Mandatory sign boards are to be in place.

4. More numbers of sprinklers is to be provided around the crusher unit to suppress dust.

The proponent should set apart Rs.13 lakh (recurring) and Rs.12 lakh(non-recurring) for taking up welfare activities for the local community in consultation with the local body. EC will be issued only after completing all the pre-mining conditions in the project site. A notarised affidavit should be submitted to this extent and also agreeing all the general and specific conditions. The proponent has submitted an affidavit vide reference  $6^{th}$  cited, satisfying all the above conditions.

- 8. Environmental Clearance as per the EIA notification 2006 is hereby accorded for the proposed quarry project of Sri.T.K.Sundaresan, Managing Director, M/s Darshan Granites Pvt. Ltd, "Aswathy", Sivankovil Road, Punalur, Kollam District, Kerala -691305 in Sy. Nos. 31/1 Part 1, Part-2, 31/1 Part-3, 30/1, 30/2 pt, 31/1-1, 31/1-2 pt, 31/1-3, 31/1-5, 31/1-6, 31/1-7, 31/1-10, 31/5, 31/6, 31/7 at Kalanjoor Village, Konni Taluk, Pathanamthitta District, Kerala for an area of 15.07 hectares, subject to the specific conditions as in para 7 above, all the environmental impact mitigation and management measures undertaken by the project proponent in the revised Form I, EMP, PFR and Mining plan submitted to SEIAA. The assurances and clarifications given by the proponent will be deemed to be a part of these proceedings as if incorporated herein. Also the general conditions for projects stipulated for mining (items 1 to 61), appended hereto will be applicable and have to be strictly adhered to.
- 9. The clearance issued will also be subject to full and effective implementation of all the undertakings given in the application form, mitigation measures as assured in the Environment Management Plan and the mining features including progressive mine closure plan as submitted with the application and relied on for grant of this clearance. The undertakings and conditions subject to all the mining features, Environmental Management Plans as undertaken in the Mining Plan and EMP submitted to SEIAA will be deemed to be part of this proceedings as conditions as undertaken by the proponent, as if incorporated herein.
- Validity of the Environmental Clearance will be five years from the date of this clearance, subject to inspection by SEIAA on annual basis and compliance of the conditions, subject to earlier review of E.C in case of violation or non-compliance of conditions or genuine complaints from residents within the security area of the quarry.
- 11. Compliance of the conditions herein will be monitored by the State Environment Impact Assessment Authority or its authorised offices and also by the regional office of the Ministry of Environment & Forests, Govt. of India, Bangalore.
  - i. Necessary assistance for entry and inspection should be provided by the project proponent and those who are engaged or entrusted by him to the staff for inspection or monitoring.
  - ii. Instances of violation if any shall be reported to the District Collector, Pathanamthitta to take legal action under the Environment (Protection) Act 1986.

iii. The given address for correspondence with the authorised signatory of the project is Sri.T.K.Sundaresan, Managing Director, M/s Darshan Granites Pvt. Ltd, "Aswathy", Sivankovil Road, Punalur, Kollam District, Kerala -691305

Sd/-JAMES VARGHESE.I.A.S, Member Secretary (SEIAA)

To,

Sri.T.K.Sundaresan,
Managing Director, M/s Darshan Granites Pvt. Ltd,
"Aswathy", Sivankovil Road,
Punalur, Kollam District,
Kerala -691305

## Copy to,

- 1. MoEF Regional Office, Southern Zone, Kendriya Sadan, 4<sup>th</sup> Floor, E&F Wing, II Block, Koramangala, Bangalore-560034.
- 2. The Additional Chief Secretary to Government, Environment Department, Government of Kerala.
- 3. District Collector, Pathanamthitta
- 4. Director, Mining & Geology, Thiruvananthapuram -4.
- 5. The Member Secretary, Kerala State Pollution Control Board
- 6. District Geologist, Pathanamthitta
- 7. Tahsildhar. Konni Taluk, Pathanamthitta
- 8. Chairman, SEIAA.
- 9. Website.
- 10. S/f
- 11. O/c

Forwarded/By Order

Administrator, SEIAA

# STATE ENVIRONMENT IMPACT ASSESSMENT AUTHORITY KERALA

# GENERAL CONDITIONS (for mining projects)

- Rain Water Harvesting facility should be installed as per the prevailing provisions of KMBR / KPBR, unless otherwise specified.
- 2. Environment Monitoring Cell as agreed under the affidavit filed by the proponent should be formed and made functional.
- 3. Suitable avenue trees should be planted along either side of the tarred road and open parking areas, if any, including of approach road and internal roads.
- 4. Maximum possible solar energy generation and utilization shall be ensured as an essential part of the project.
- 5. Sprinklers shall be installed and used in the project site to contain dust emissions.
- 6. Eco-restoration including the mine closure plan shall be done at the own cost of the project proponent.
- 7. At least 10 percent out of the total excavated pit area should be retained as water storage areas and the remaining area should be reclaimed with stacked dumping and overburden and planted with indigenous plant species that are eco-friendly, if no other specific condition on reclamation of pit is stipulated in the E.C.
- 8. Corporate Social Responsibility (CSR) agreed upon by the proponent should be implemented
- 9. The lease area shall be fenced off with barbed wires to a minimum height of 4ft around, before starting of mining. All the boundary indicators (boards, stores, markings, etc) shall be protected at all times and shall be conspicuous.
- Warning alarms indicating the time of blasting (to be done at specific timings) has to be arranged as per stipulations of Explosive Department.
- 11. Control measures on noise and vibration prescribed by KSPCB should be implemented.
- 12. Quarrying activities should be limited to day time as per KSPCB guidelines/specific conditions.
- Blasting should be done in a controlled manner as specified by the regulations of Explosives Department or any other concerned agency.
- 14. A licensed person should supervise/ control the blasting operations.
- 15. Access roads to the quarry shall be tarred to contain dust emissions that may arise during transportation of materials.
- 16. Overburden materials should be managed within the site and used for reclamation of mine pit as per mine closure plan / specific conditions.
- Height of benches should not exceed 5 m, and width should not be less than 5 m, if there is no mention is the mining plan/specific condition.
- 18. Mats to reduce fly rock blast to a maximum of 10 PPV should be provided.
- 19. Maximum depth of mining from general ground level at site shall not exceed 10m
- 20. No mining operations should be carried out at places having a slope greater than 45°.
- Acoustic enclosures should have been provided to reduce sound amplifications in addition to the provisions of green belt and hollow brick envelop for crushers so that the noise level is kept within prescribed standards given by CPCB/KSPCB.
- 22. The workers on the site should be provided with the required protective equipment such as ear muffs, helmet, etc.
- 23. Garland drains with clarifiers to be provided in the lower slopes around the core area to channelize storm water.
- 24. The transportation of minerals should be done in covered trucks to contain dust emissions
- 25. The proponent should plant trees at least 5 times of the loss that has been occurred while clearing the land for the project.
- 26. Disposal of spent oil from diesel engines should be as specified under relevant Rules/Regulations.
- 27. Explosives should be stored in magazines in isolated place specified and approved by the Explosives Department.
- A minimum buffer distance of 100m from the boundary of the quarry to the nearest dwelling unit or other structures, not being any facility for mining shall be provided.
- 29. 100 m buffer distance should be maintained from forest boundaries.

- 30. Consent from Kerala State Pollution Control Board under Water and Air Act(s) should be obtained before initiating mining activity.
- 31. All other statutory clearances should be obtained, as applicable, by project proponents from the respective competent authorities including that for blasting and storage of explosives.
- 32. In the case of any change(s) in the scope of the project, extent quantity, process of mining technology involved or in any way affecting the environmental parameters/impacts as assessed, based on which only the E.C is issued, the project would require a fresh appraisal by this Authority, for which the proponentshall apply and get the approval of this Authority.
- 33. The Authority reserves the right to add additional safeguard measures subsequently, if found necessary, and to take action including revoking of the environment clearance under the provisions of the Environment (Protection) Act, 1986, to ensure effective implementation of the suggested safeguard measures in a time bound and satisfactory manner.
- 34. The stipulations by Statutory Authorities under different Acts and Notifications should be complied with, including the provisions of Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and control of Pollution) act 1981, the Environment (Protection) Act, 1986, the Public Liability (Insurance) Act, 1991 and EIA Notification, 2006.
- 35. The project proponent should advertise in at least two local newspapers widely circulated in the region, one of which (both the advertisement and the newspaper) shall be in the vernacular language informing that the project has been accorded Environmental Clearance and copies of clearance letters are available with the State Environment Impact Assessment Authority (SEIAA) office and may also be seen on the website of the Authority at www.seiaakerala.org. The advertisement should be made within 10 days from the date of receipt of the Clearance letter and a copy of the same signed in all pages should be forwarded to the office of this Authority as confirmation.
- 36. A copy of the clearance letter shall be sent by the proponent to concerned Grama Panchayat/ District Panchayat/ Municipality/Corporation/Urban Local Body and also to the Local NGO, if any, from whom suggestions / representations, if any, were received while processing the proposal. The Environmental Clearance shall also be put on the website of the company by the proponent.
- 37. The proponent shall submit half yearly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) and upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the respective Regional Office of MoEF, Govt. of India and also to the State Environment Impact Assessment Authority (SEIAA) office.
- 38. The details of Environmental Clearance should be prominently displayed in a metallic board of 3 ft x 3 ft with green background and yellow letters of Times New Roman font of size of not less than 40. Sign board with extent of lease area and boundaries shall be depicted at the entrance of the quarry, visible to the public
- 39. The proponent should provide notarized affidavit (indicating the number and date of Environmental Clearance proceedings) that all the conditions stipulated in the EC shall be scrupulously followed.
- 40. No change in mining technology and scope of working should be made without prior approval of the SEIAA, No further expansion or modifications in the mine shall be carried out without prior approval of the SEIAA, as applicable.
- 41. The Project proponent shall ensure that no natural water course and/or water resources shall be obstructed due to any mining operations. Necessary safeguard measures to protect the first order streams, if any, originating from the mine lease shall be taken.
- 42. Monitoring of Ambient Air Quality to be carried out based on the Notification 2009, as amended from time to time by the Central Pollution Control Board. Water sprinkling should be increased at places loading and unloading points & transfer point to reduce fugitive emissions.
- 43. The top soil, if any, shall temporarily be stored at earmarked site(s) only for the topsoil shall be used for land reclamation and plantation. The over burden (OB) generated during the mining operations shall be stacked at earmarked dump site(s) only. The maximum height of the dumps shall not exceed 8m and width 20m and overall slope of the dumps shall be maintained to 45°. The OB dumps should be scientifically vegetated with suitable native species to prevent erosion and surface run off. In critical areas, use of geo textiles shall be undertaken for stabilization of the dump. The entire excavated area shall be backfilled. Monitoring and management of rehabilitated areas should continue until the vegetation becomes self-sustaining.

- 44. Catch drains and siltation ponds of appropriate size shall be constructed around the mine working, mineral and OB dumps to prevent run off of water and flow of sediments directly into the river and other water bodies. The water so collected should be utilized for watering the mine area, roads, green belt development etc. The drains shall be regularly desilted particularly after monsoon and maintained properly.
- 45. Effective safeguard measures such as regular water sprinkling shall be carried out in critical areas prone to air pollution and having high levels of PM<sub>10</sub> and PM<sub>2.5</sub> such as haul Road, loading and unloading points and transfer points it shall be ensured that the Ambient Air Quality parameters conform to the norms prescribed by the Central Pollution Control Board in this regard.
- 46. Fugitive dust emissions from all the sources should be controlled regularly. Water spraying arrangement on haul roads, loading and unloading and at transfer points should be provided and properly maintained.
- 47. Measures should be taken for control of noise levels below 85 dBA in the work environment.
- 48. A separate environmental management cell with suitable qualified personnel should be set-up under the control of a Senior Executive, who will report directly to the Head of the Organization.
- 49. The funds earmarked for environmental protection measures and CSR activate should be kept in separate account and should not be diverted for other purpose. Year wise expenditure should be reported to the State Environment Impact Assessment Authority (SEIAA) office.
- 50. The Regional Office of MOEF & CC located at Bangalore shall monitor compliance of the stipulated conditions. The project authorities should extend full cooperation to the officer (S) of the Regional Office by furnishing the requisite data/information/monitoring reports.
- 51. Any appeal against this Environmental Clearance shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.
- 52. Concealing the factual data or submission of false/fabricated data and failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of Environment (Protection) Act, 1986.
- 53. The SEIAA may revoke or suspend the order, for non implementation of any of the specific or thisimplementation of any of the above conditions is not satisfactory. The SEIAA reserves the right to alter/modify the above conditions or stipulate any further condition in the interest of environment protection.
- 54. The above conditions shall prevail notwithstanding anything to the contrary, in consistent, or simplified, contained in any other permit, license on consent given by any other authority for the same project.
- 55. This order is valid for a period of 5 years or the expiry date of mine lease period issued by the Government of Kerala, whichever is earlier.
- 56. The Environmental Clearance will be subject to the final order of the courts in any pending litigation related to the land or project, in any court of law.
- 57. The mining operation shall be restricted to above ground water table and it should not intersect ground water table.
- All vehicles used for transportation and within the mines shall have 'PUC' certificate from authorized pollution taking centre. Washing of all vehicles shall be inside the lease area'.
- 59. Project proponent should obtain necessary prior permission of the competent authorities for drawal of requisite quantity of surface water and ground water for the project.
- 60. Regular monitoring of flow rates and water quality upstream and downstream of the springs and perennial nallahs flowing in and around the mine lease area shall be carried out and reported in the six monthly reports to SEIAA.
- Occupational health surveillance program of the workers should be under taken periodically to observe any contractions due to exposure to dust and take corrective measures, if needed.

THE STATE OF THE S

For Member Secretary, SEIAA Kerala

